


TABLE "A"

6" PIPE	2'-6"
8" PIPE	2'-6"
10" PIPE	3'-0"
12" PIPE	3'-0"
15", 16" PIPE	3'-6"
18" PIPE	4'-0"
24" PIPE	4'-0"

NOTES:

1. FILL AREAS SHALL BE FILLED AND COMPACTED PRIOR TO INSTALLATION OF SEWER MAINS. 90% COMPACTION PER ASTM D-1557 REQUIRED IN FILL AREAS. REPORTS REQUIRED PRIOR TO TRENCHING.
2. BEDDING SHALL BE PEA GRAVEL OR $\frac{5}{8}$ " MINUS CRUSHED SURFACING.
3. TRENCH DAMS SHALL BE INSTALLED PER STD. PLAN NO. 11 IN WET AREAS AS DIRECTED BY THE ENGINEER.
4. PUMPING SOILS SHALL BE REMOVED FROM THE TRENCH BACKFILL IMMEDIATELY.
5. REFER TO STD. PLAN NO. 8 (TYP. TRENCH SECTION) IN RIGHTS OF WAY OR OTHER PAVED AREAS. IF EASEMENT FALLS WITHIN A FUTURE OR PROPOSED PAVED AREA.
6. EASEMENT AREAS THAT WILL BE FUTURE RIGHT OF WAYS OR PAVED AREAS COMPACT BACKFILL TO 95% OF MAX. DENSITY.



**Woodinville
Water District**

**TYPICAL TRENCH SECTION
IN EASEMENT AREAS**



**SEWER STD.
PLAN NO. 9**

REVISION DATE
12-20