



NOTES:

1. CONTRACTOR SHALL LOCATE DIA. X 6" TEE AT HIGH POINT IN THE MAIN. THE MAINLINE GENERALLY NEEDS TO BE DEEPER THAN 3' TO PROVIDE BURY DEPTH AT THE AIR RELEASE BOX AND 2" GALV. DISCHARGE PIPING. SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. SEE STANDARD PLAN 6 FOR VALVE BOX REQUIREMENTS.
3. METAL LID TO HAVE A PICK HOLE OR PICK NOTCH. METER FLAP NOT ALLOWED.
4. AIR VAC PIPING TO BE PAINTED (2) COATS OF SHERWIN WILLIAMS INDUSTRIAL URETHANE ALKYD B54Y157 SAFETY YELLOW. VALVE & AIR VAC BOX LIDS TO BE PAINTED (2) COATS OF SHERWIN WILLIAMS INDUSTRIAL URETHANE ALKYD B54T00154 SW4086 SAFETY BLUE.
5. AIR RELEASE AND PIPING SHALL BE INCLUDED IN PRESSURE TESTING.
6. PLACE VALVE TYPE AND SIZE INDICATOR IN VALVE CHAMBER. SEE STANDARD PLAN 23.



**Woodinville
Water District**

**AIR RELEASE
ASSEMBLY**



**WATER STD.
PLAN NO. 11**

REVISION DATE
12-20