



NOTES:

1. THE CONTRACTOR SHALL OFFSET STAKE ALL EXISTING VALVE BOX LOCATIONS. DIMPLES SHALL BE LEFT IN THE OVERLAY FOR LOCATING PURPOSES AND EMERGENCY ACCESS.
2. VALVE BOX & LID TO BE EAST JORDAN IRON WORKS PRODUCT NO. 85552737 CATALOG NO. 8555.
3. VALVE BOX LIDS TO BE A MIN. 3.5 INCHES IN OVERALL DEPTH. LOCKING VALVE BOX LIDS REQUIRED IF LIDS WILL NOT STAY PUT DUE TO TRAFFIC OR AS REQUIRED BY THE DISTRICT.
4. SAWCUT VALVE BOX COMPONENTS BROKEN OR JAGGED VALVE BOX SECTIONS NOT ACCEPTABLE.
5. USE OF OVERLAY RINGS REQUIRED APPROVAL FROM WWD AND RIGHT OF WAY JURISDICTION.
6. VALVE BOX LIDS TO BE PAINTED (2) COATS OF SHERWIN WILLIAMS INDUSTRIAL URETHANE ALKYD B54T00154 SW4086.
7. VALVE BOXES SHALL BE ADJUSTED AFTER OVERLAY AND PATCHED AS SHOWN ABOVE. VALVES SHALL BE ADJUSTED WITHIN (3) WORKING DAYS OF THE OVERLAY.
8. IF ANY PART OF THE VALVE BOX NEEDS TO BE REPLACED INSTALLATION SHALL BE PER STANDARD PLAN NO. 6.



**Woodinville
Water District**

**VALVE BOX ADJUSTMENT
IN ASPHALT OVERLAY**



**WATER STD.
PLAN NO. 6B**

REVISION DATE

3-16