

SEE STANDARD PLAN 13B FOR MATERIAL LIST

NOTE - CIRCLED NUMBERS ABOVE REFER TO MATERIALS LISTED ON STD PLAN 13B.


NOTES

1. LOT CORNERS AND PROPERTY LINES MUST BE ESTABLISHED BEFORE SERVICES ARE INSTALLED.
2. CONTRACTOR TO PROVIDE ALL MATERIALS PER STD. PLAN 13M.
3. CONTACTOR SHALL SCHEDULE SERVICE FLUSH WITH THE DISTRICT INSPECTOR. TAPPING COUPON TO BE PRESENTED TO THE DISTRICT INSPECTOR. SERVICES TO BE TESTED UNDER MAINLINE PRESSURE.
4. TRACE WIRES MUST BE VISIBLE IN METER BOX.
5. NO SPLICES ALLOWED IN SERVICE LINES.
6. CORP STOP LOCATION SHALL BE OFFSET PRECISELY FOR GPS SURVEY.
7. METER INSTALLATION BY THE DISTRICT. METER WILL NOT BE SET UNTIL PROJECT ACCEPTED.
8. METER BOX SHALL BE PERPENDICULAR TO SIDEWALK, PROPERTY LINE, OR AS DIRECTED. TOP OF BOX SHALL BE FLUSH WITH FINISH GRADE.
9. SINGLE FAMILY FIRE OR IRRIGATION SERVICES SHALL HAVE BACKFLOW PROTECTION PER STANDARD PLAN 21. BACKFLOW BOX SHALL BE INLINE BEHIND METER BOX.
10. NO METER OR DCVA BOXES ALLOWED IN DRIVEWAYS OR HARD SURFACES.
11. METER BOXES INSTALLED ON SLOPES MAY REQUIRE A LANDSCAPE BLOCK WALL TO ACHIEVE A CLEAR AND LEVEL AREA.
12. IF AN EXISTING SERVICE IS BEING MOVED TO A NEW LOCATION INSULATE METER PER WATER STANDARD PLAN 13B NOTE 8.
13. ALL FITTINGS AND BRASS COMPONENTS SHALL CONFORM TO THE LATEST VERSIONS OF NSF 61 AND ANSI/AWWA STANDARD C800 AND SHALL BE STAMPED / EMBOSSED TO SHOW THE PRODUCT IS MADE FROM A NO LEAD ALLOY.



Woodinville
Water District

SINGLE FAMILY
SERVICE INSTALLATION



WATER STD.
PLAN NO. 13

REVISION DATE

04/25