



**NOTES:**

1. THIS STANDARD PLAN IS APPLICABLE FOR NEW OR UPDATED CONSTRUCTION THAT IS NOT PART OF A DEVELOPER'S EXTENSION.
2. IT SHALL BE THE OWNER'S RESPONSIBILITY TO INSURE THAT THE SERVICE LINES AND METER SIZES ARE ADEQUATE TO SERVE THE DOMESTIC & FIRE SPRINKLER OR IRRIGATION SYSTEMS. REFER TO LARGER METER AND BACKFLOW DEVICE DETAILS FOR SYSTEMS REQUIRING PIPE AND METER LARGER THAN 1".
3. AFTER PROJECT ACCEPTANCE AND METER SET FEES HAVE BEEN PAID, THE METERS WILL BE INSTALLED BY THE DISTRICT.
4. INSTALL DOMESTIC, FIRE, AND/OR IRRIGATION SERVICE IN ACCORDANCE WITH STANDARD PLAN 13 (SINGLE FAMILY DOMESTIC SERVICE). BACK OF METER BOX SHALL BE PLACED AT THE RIGHT OF WAY LINE OR IN THE UTILITY EASEMENT AS SHOWN.
5. THE BACKFLOW PREVENTION DEVICE SHALL BE A DOUBLE CHECK VALVE ASSEMBLY AS APPROVED BY THE WASHINGTON STATE DEPARTMENT OF HEALTH OR AS DIRECTED BY THE DISTRICT. MINIMUM SIZE OF BACKFLOW DEVICE SHALL BE 1" OR MATCH METER SIZE.
6. NO CHEMICALS ARE ALLOWED IN THE FIRE SPRINKLER PIPING SYSTEM.
7. THE BACKFLOW PREVENTION ASSEMBLY SHALL BE INSTALLED BY THE OWNER. SEE STANDARD PLAN NO. 21. THE BACKFLOW DEVICE SHALL NOT BE INSTALLED IN A BUILDING.
8. FIRE SPRINKLER SYSTEMS SHALL BE DESIGNED IN ACCORDANCE WITH THE LOCAL FIRE MARSHAL'S REQUIREMENTS AND HAVE FIRE MARSHAL APPROVAL.
9. NO METER OR DCVA BOXES ALLOWED IN DRIVEWAYS OR HARD SURFACE AREAS.
10. INSPECTION REQUIRED ON FIRE SERVICE AND BACKFLOW ASSEMBLY INSTALLATION PRIOR TO BACKFILL. CALL 425-487-4100 TO SCHEDULE.
11. INITIAL TEST OF THE DCVA IS REQUIRED TO ESTABLISHMENT OF WATER SERVICE. TEST RESULTS SHALL BE SENT TO WOODINVILLE WATER DISTRICT. ANNUAL TESTING OF THE DCVA BY A CERTIFIED BACKFLOW ASSEMBLY TESTER IS REQUIRED BY THE OWNER. TEST RESULTS SHALL BE SUBMITTED TO THE WOODINVILLE WATER DISTRICT.



**Woodinville  
Water District**

**1" SINGLE FAMILY  
DOMESTIC /FIRE  
/IRRIGATION  
SERVICE CONNECTION**



**WATER STD.  
PLAN NO. 14**

REVISION DATE  
**04/25**